



Bid – Sinkhole Repairs 2026-0406
Addendum #1 - dated April 17, 2026

1. Can I go and visit the site or do I need to set up a time to go look at it?
 - a. You are able to visit the site at any time
2. At what point does the Engineer want the 6-hole driller to bedrock or voids. Before excavation starts or after we dig down the 432 elevation.
 - a. The original design intent was to have the contractor drill the holes before excavation starts and do their best to keep them clean knowing some debris will get in the holes, then plan to pressure wash and flush out holes after excavation as method of cleaning when cleaning rock surface prior to grouting the pipe. Otherwise, they can be drilled after the hole is excavated if there enough area within the limits of disturbance to create a ramp in and out of the excavation for a tracked drill rig
 - b. If the holes are drilled prior to excavation, no additional footage will be paid for.
3. Does the standpipe need to be wrapped in fabric, this might clog up the holes in the pipe quicker.
 - a. The entire rock layer is wrapped in geotextile so very few fines should reach the pipe.
4. In the injection well you call out only 13 ft of rock and the rest with dirt, capped with topsoil. Should there be rock all the way up 30” below top of pipe. Yes there is fabric between, but it might stop up quicker. Just making sure this is what you want.
 - a. Understood but surface water is meant to enter through the pipe not by infiltrating into the ground.
 - b. Yes, detail 1 on C7.05 shows a 12” band of 57 Stone all the way up to the 30” below top of pipe
5. Are there any addendums or additional docs other than "bid pdf, construction drawings, geo report"?
 - a. None other than this addendum.
6. What is the anticipated start date?
 - a. As soon as possible